

BRUHAT BANGALORE MAHANAGARA PALIKE**Name of work: Improvements to SWD in Ward No.08 Kodigehalli****Agency:-M/s KRIDL****SCHEDULE-B**

Sl No	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	2388.96	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	220.40	Rupees Two Hundred Twenty And Paise Forty Only
2	137.38	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms [^] thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5505.64	Rupees Five Thousand Five Hundred Five And Paise Sixty Four Only
3	347.70	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.	Sqm	273.48	Rupees Two Hundred Seventy Three And Paise Forty Eight Only
4	2805.60	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	379.48	Rupees Three Hundred Seventy Nine And Paise Forty Eight Only
5	367.49	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.0.69cum and fine aggregates @ 0.460cum, with superplasticiser @3lts conforming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Fifty Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BANGALURU-560 010
Contractor

Executive Engineer
Project Division
Yelahanka Zilla

SI No	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
6	19.03	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tn	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three And Paise Ninety Six Only
7	998.10	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete.	Sqm	2111.00	Rupees Two Thousand One Hundred Eleven Only
8	36.00	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer in charge	Sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
9		GST		12.00%	Twelve Percent

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

13/12/15